

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued May 15, 1967.RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dorset Company
 Complete Address: 610 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103
 Lease Name Mott Well No. # 1
 Location C NW SW Sec. 32 Twp. 32 Rge. 5 (E) (W)
 County Harper Total Depth 3733'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated: _____
 Plugging Contractor: Winfield Oil Field Service, Inc.
 Address: Box 952, Winfield, Kansas License No. 531
 Operation Completed: Hour 10:30AM Day 20th Month May Year 1967

The Above well was plugged as follows:

281' of 8 5/8" surface pipe, cemented with 225 sacks. 3733' of 5 1/2" long
string, cemented with 50 sacks. This is an open hole. Bottom of the hole
was sanded to 3685', and cemented with 5 sacks, through the dump bailer.
3200' of 5 1/2" long string was recovered from the hole. Fluid level in the
hole was at 260', bridge plug and rock bridge from 260' to 250', and
cemented with 20 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging SupervisorDATE 5/23/67INV. NO. 5269-W