

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 16 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Banning Well No. # 1

Location NE NE NW Sec. 16 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4520'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 4:00PM Day 14th Month Nov. Year 1966

The Above well was plugged as follows:

197' of 8 5/8" surface pipe, cemented with 100 sacks. 4518' of 4 1/2" long  
string, cemented with 100 sacks. Top perferation 4440'. Bottom of the  
hole was sanded to 4260', and cemented with 3 sacks, through the dump  
bailer. 3666' of 4 1/2" long string was recovered from the hole. Fluid in  
the hole was bailed down to 230', rock bridge from 230' to 210', and  
cemented with 25 sacks. Hole was filled with mud to 40', rock bridge from  
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Aubie Elving  
Well Plugging Supervisor

DATE 11/16/66  
INV. NO. 4292-W