

15-025-30075-0000
Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JAN 3 1968
1-3-68

Operator's Full Name J.M. Huber Corporation

Complete Address: Box 831, Borger, Texas

Lease Name York Well No. 1

Location C. NW Sec. 33 Twp. 32 Rge. 21 ~~(E)~~ (W)

County Clark Total Depth 5425'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Daco Lease & Well Service

Address: Borger, Texas License No. 138

Operation Completed: Hour 6:00PM Day 30 Month 12 Year 1967

The Above well was plugged as follows:

8 5/8" to 712' circulated w/ cement. 4 1/2" to 5373' cemented.

Top perforations 5321' Plug bottom w/, 20 sacks cement.

Top of cement 5124' Mud 5124' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 3529' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-3-68

INV. NO. 7036-W

Signed: Edgar J. Evers
Well Plugging Supervisor