



15-025-30075-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

JAN 3 1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Casey of J.M. Huber Corp. has this date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: J.M. HUBER Corporation

Complete Address: Box 831, Borger, Texas

Lease Name: York Well No. 1

Location: C NW Sec. 33 Twp. 32 Rge. 21 (E) (W)

County Clark Total Depth 5425' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 712' circulated w/ cement. 4 1/2" to 5373' cemented

Top perforations 5321' Plug bottom w/ 20 sacks cement.

Top of cement 5124' Mud 5124' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

*Edgar J. Green*  
Conservation Division Agent