



CP

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 W. Douglas Wichita, Ks

Lease Name: Muir G Well No. 1

Location: NW/NE/NW Sec. ²⁸21 Twp. 31s Rge. 9 (E)(W) W

County: Harper Total Depth 4470 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

250 ft of 8 5/8 surface pipe cemented with 245 sacks. Fill
hole to 240 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to base of cellar.
2 sacks cement in rat hole.

Very truly yours,

L. Russell Brinton
Conservation Division Agent