



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 5 1962
 11-5-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Oct. 30, 1962

Dear Sir:

Mr. D. B. Pully of Forbes Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. D. B. Pully guarantees payment of the plugging fee.

Operator's full Name: MULL Drilling Co.
~~Forbes Caseing Pulling Co.~~

Complete Address: 670 4th Nat'l Bk. Bldg. Wichita, KANSAS
~~Box 221 - St. Bond, Kansas.~~

Lease Name: Muir #1 Well No. #1

Location: NE-SE-NE Sec. 28 Twp. 31 Rge. 9 (E) (W) X

County Harper Total Depth 4499' Oil Well Aband.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

4495' of 4 1/2" long string cemented with 125 sacks cement.
4 1/2" sanded to 4400' and 3 sacks cement. 200' of 8 5/8" surface
pipe circulated with cement. Hole filled to 180' with mud,
10' rock bridge and 20 sacks cement. Hole filled to 40'
with mud, 10' rock bridge and 10 sacks cement to bottom of
cellar.

Very truly yours,

Herman Justus
 Conservation Division Agent