



JP

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buller of Gabbert & Jones, Inc. has this date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: Keener Oil Co.

Complete Address: 406 NBT Bldg. Tulsa, OK

Lease Name: Weede Well No. 1

Location: 150 ft NE/C/NW/NW Sec. 3 Twp. 32s Rge. 5 (E)(W) W

County: Harper Total Depth 4643 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buller was instructed to plug the well as follows:
239 ft 8 5/8 surface pipe cemented with 200 sacks. Pump
25 sacks cement to 3200 ft. 2nd plug at 250 ft with 30
sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks
cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

L. Russell Biberstein
Conservation Division Agent