

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed April 21, 1967.

Dear Sir:

Mr. Lester Mercer of Midwest Oil Corporation has this

date requested permission to plug the following described well:

Mr. Mercer guarantees payment of the plugging fee.

Operator's full Name: Midwest Oil Corporation

Complete Address: 1418 Liberty Bldg., Oklahoma City, Oklahoma

Lease Name: Ballet Ranch Well No. # 9

Location: 1220' FWL & 2340' FSL Sec. 31 Twp. 34 Rge. 15 (E)(W) W

County Barber Total Depth 5025' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mercer was instructed to plug the well as follows:

1008' of 8 5/8" surface pipe, cement circulated with 550 sacks. Fill
hole with drilling mud to 500', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge rat & mouse holes and cement with 5 sack

Very truly yours,

Archie Elving
Conservation Division Agent