

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1964
6-19-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company
Complete Address: P. O. Box 649, McCook, Nebraska
Lease Name Birdie Clarke Well No. # 2
Location NE NW SE Sec. 12 Twp. 34 Rge. 14 (E) (W) W
County Barber Total Depth 4925
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Leben Drilling Inc.
Address: 912 Central Bldg., Wichita, Kansas License No.
Operation Completed: Hour 2:00AM Day 17th Month June Year 1964

The Above well was plugged as follows:
485' of 8 5/8" surface pipe, cemented with 275 sacks. Bottom of the hole
was cemented with 50 sacks, pumped through 4900' of drill pipe. Hole was
filled with drilling mud to 475', 1st cementing plug, bridged with hulls,
and cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged with hulls, and cemented
with 10 sacks to base of the cellar. Rat hole bridged and cemented with
5 sacks. This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/19/64
INV. NO. 9323-U

Signed: Archie Elving
Well Plugging Supervisor