

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1965
9-10-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett
Complete Address: 1212 Union National Bldg., Wichita, Kansas
Lease Name Whittlesey Estate Well No. # 1
Location C S/2 NE Sec. 8 Twp. 34 Rge. 14 (E) (W) W
County Barber Total Depth 4797'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Comstock Pipe Pulling, Inc.
Address: Stafford, Kansas License No. 490
Operation Completed: Hour 7:15 PM Day 7th Month Sept. Year 1965

The Above well was plugged as follows:

227' of 13 3/8" surface pipe, cement circulated. 4797' of 4 1/2" long string,
cemented with 125 sacks. Plug back to 4760'. Top perforation 4710'. Bottom
of the hole was squeezed with 100 sacks of cement. Cement and plug was
pumped to 4327'. Fluid in the hole was bailed down to 200', rock bridge
from 200' to 190', and cemented with 5 yards of Ready-Mix cement. Hole
was filled with mud to 35', rock bridge from 35' to 25', and cemented
with 1 yard of Ready-Mix cement to the base of the cellar.
4220' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/10/65

INV. NO. 1779-W