

**KANSAS**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 17 1965  
11-17-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Davis Ranch "E" Well No. # 1

Location C NW Sec. 6 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4960'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30 PM Day 15th Month Nov. Year 1965

The Above well was plugged as follows:

458' of 13 3/8" surface pipe, cement circulated. 4960' of 4 1/2" long  
string, cemented with 150 sacks. Plug back to 4877'. Top perforation  
4871'. Bottom of the hole was sanded to 4860', and cemented with 3  
sacks. 4000' of 4 1/2" long string was recovered from the hole. Hole was  
filled with mud to 300', rock bridge from 300' to 290', and cemented  
with 40 sacks. Hole was filled with mud to 40', rock bridge from 40'  
to 25', and cemented with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11/17/65  
INV. NO. 2201-W