

*10*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1965  
8-20 65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Sooter "A" Well No. # 1

Location NW NE SW Sec. 2 Twp. 34 Rge. 14 (E) (W)W

County Barber Total Depth 4810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00 AM Day 19th Month August Year 1965

The Above well was plugged as follows:

370' of 8 5/8" surface pipe, cemented with 550 sacks. Fluid level in the  
hole was at 225'. 1st cementing plug and 1 sack of hulls was pushed in  
fluid to 300', and cemented with 25 sacks, through the drill pipe. Hole  
was filled with drilling mud to 40', 2nd cementing plug, bridged solid  
with hulls on fluid at 40', and cemented with 10 sacks to the base of  
the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/20/65

INV. NO. 1667-W