

15-007-10357-0000

Form CP-3
Rev. 6-26-62

~~10~~ KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1966
16-31-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc., c/o Mountain Iron & Supply Company

Complete Address: 200 Misco Bldg., Wichita, Kansas

Lease Name Good Well No. # 1

Location SW SW SW Sec. 22 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4842'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling Company

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 9:00AM Day 29th Month Oct. Year 1966

The Above well was plugged as follows:

309' of 8 5/8" surface pipe, cement circulated. 4842' of 5 1/2" long string,
cemented with 100 sacks. Top perferation 4724'. Bottom of the hole was
sanded to 4660', and cemented with 5 sacks. 3815' of 5 1/2" long string was
recovered from the hole. Fluid level in the hole was at 140'. 10 sacks
of Gel-Mud and 75 sacks of cement was pumped into the surface pipe,
through an 8 5/8" swage to a pressure of 400 lbs.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/31/66
INV. NO. 4204-u