

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Kansas

Lease Name McBrayer Well No. # 1

Location C NW SW SW Sec. 14 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4955'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: E. K. Edmiston Drilling Company

Address: 501 First National Bank Bldg., Wichita, Kans. License No. _____

Operation Completed: Hour 7:30 AM Day 29th Month June Year 1965

The Above well was plugged as follows:

335' of 10 3/4" surface pipe, cement circulated with 250 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged solid
with hulls on fluid at 300', and cemented with 30 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 15 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED
JUL 1 1965
DATE 7/1/65
CONSERVATION DIVISION
INV. NO. Wichita 2-12-2 - W
7-1-65

Signed: Archie Elving
Well Plugging Supervisor