

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1963

4-1-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Lovell of Texaco Oil Co. has this

date requested permission to plug the following described well:

Mr. Lovell guarantees payment of the plugging fee.

Operator's full Name: Texaco Oil Co.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Stranathan Well No. # 1

Location: App. C-SUNNE 1980' SNL & 1930' WEL Sec. 26 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4800 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lovell was instructed to plug the well as follows:

261' of 8 5/8" surface pipe circulated with 200 sacks  
cement. Fill hole with mud to 240', 1st cementing plug,  
1/2 sack hulls, cement 35 sacks. Fill hole to 40' with mud,  
2nd cementing plug, 1/2 sack hulls, cement with 10 sacks  
to base cellar. Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent