

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1964

6-A-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Fred Glick of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Glick guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name: Birdie Clarke Well No. # 2

Location: NE NW SE Sec. 12 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4925 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Glick was instructed to plug the well as follows:

485' of 8 5/8" surface pipe, cemented with 275 sacks. Fill  
hole with drilling mud to 475', 1st cementing plug, bridge with  
hulls, and cement with 25 sacks. Fill hole with drilling mud to  
40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent