

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1965
3-29-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ted Dix of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name: R. G. Anderson Well No. # 1

Location: App. SE NE NW Sec. 12 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4863 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dix was instructed to plug the well as follows:

378' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 275', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls and cement

with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent