

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-007-21,414-0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Gore Oil Company OPERATOR'S LICENSE NO. 5552 *6/90*

ADDRESS 125 N. Market, Suite 1750 - Wichita, Ks 67202 PHONE # (316) 263-3535

LEASE (FARM) Burgess "B" WELL NO. 4 WELL LOCATION SW SE NW COUNTY Barber
SEC. 35 TWP. 34s RGE. 12 (E or W) TOTAL DEPTH 4840' PLUG BACK TD 4829'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 817' CEMENTED WITH 575 SACKS

CASING SIZE 4 1/2" SET AT 4839' CEMENTED WITH 225 SACKS

PERFORATED AT 4770'-4780'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING To pull casing. Plug back with sand to 4720'. Dump 4 sx cement. Plug with 300# hulls, 10 sx gel, 50 sx 60/40 - 6%, 100# hulls, 10 sx gel, 100 sx 60/40 - 6% to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 15, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Scott W Scheuerman PHONE # (316) 263-3535

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202
STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Clarke Corporation LICENSE NO. 5105 *6/90*

ADDRESS Box 187, Medicine Lodge, KS 67104 PHONE # (316) 886-5665

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

2-14-90

SIGNED: *Scott W Scheuerman*
(Operator or Agent)

DATE: February 13, 1990

①



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HEALEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE
 MAY 15 1990
 EXPIRES

February 15, 1990
 NOTICE OF RECEIPT OF
 WELL PLUGGING APPLICATION

Gore Oil Company
 125 N. Market, Suite 1750
 Wichita, KS 67202

Burgess "B" 4
 SW SE NW
 Sec. 35-34-12W
 Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
 Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760