

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-007-21,701-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Gore Oil Company OPERATOR'S LICENSE NO. 5552

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202 PHONE # (316) 263-3535

LEASE (FARM) Morton "B" WELL NO. 2 WELL LOCATION NW NE NE COUNTY Barber

SEC. 35 TWP. 34s RGE. 12 (E) or (W) TOTAL DEPTH 4848' PLUG BACK TD 4831'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 331' CEMENTED WITH 225 SACKS

CASING SIZE 4 1/2" SET AT 4847' CEMENTED WITH 225 SACKS

PERFORATED AT 4760'-4784'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING To pull casing. Plug back with sand to 4710'. Dump 4 sx cement. Plug with 300# hulls, 10 sx gel, 50 sx 60/40 - 6%, 100# hulls, 10 sx gel, 100 sx 60/40 - 6% to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? n/a IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 15, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Scott W Scheuerman PHONE # (316) 263-3535

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202

PLUGGING CONTRACTOR Clarke Corporation LICENSE NO. 5105

ADDRESS Box 187, Medicine Lodge, KS 67104 PHONE # (316) 886-5665

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED
FEB 14 1990
2-14-90
CONSERVATION DIVISION
Wichita, Kansas

SIGNED: Scott W Scheuerman
(Operator or Agent)

DATE: February 13, 1990



Kansas Corporation Commission

MIKE HAYCEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
MAY 15 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

February 15, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Gore Oil Company
125 N. Market, Suite 1750
Wichita, KS 67202

Morton "B" 2
NW NE NE
Sec. 35-34-12W
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760