

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-007-21,236-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Gore Oil Company OPERATOR'S LICENSE NO. 5552

ADDRESS 125 N. Market, #1750, Wichita, KS 67202 PHONE # (316) 263-3535

LEASE (FARM) Morton "A" WELL NO. 3 WELL LOCATION SW SW SW COUNTY Barber

SEC. 35 TWP. 34s RGE. 12 (E) or (W) TOTAL DEPTH 4850' PLUG BACK TD 4832'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 10 3/4" SET AT 310' CEMENTED WITH 300 SACKS

CASING SIZE 4 1/2" SET AT 4849' CEMENTED WITH 225 SACKS

PERFORATED AT 4788'-4792' Mississippi

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING To pull casing. Dump sand to 50' above Mississippi perms.

5 sx cement on top of sand. Pump down 10 3/4" casing; 4 sx cottonseed hulls in 10 sx gel. 50 sx 60/40 Pozmix. 10 sx gel, 100 sx 60/40 Pozmix to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 6, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Reh PHONE # (316) 672-3236

ADDRESS Star Route, Pratt, KS 67124

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 7718

ADDRESS Box 963, Pratt, KS 67124 PHONE # (316) 672-5593

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Scott W Scheuerman
(Operator or Agent)

DATE: November 1, 1989
Scott W Scheuerman, Petroleum Engineer

RECEIVED
STATE CORPORATION COMMISSION
NOV - 2 1989
11-2-89
CONSERVATION DIVISION
WICHITA, KANSAS

①



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

THIS NOTICE
FEB 03 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

November 3, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Gore Oil Company
125 N. Market, #1750
Wichita, KS 67202

Morton "A" 3
SW SW SW
35-34-12W
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS. 67801
(316) 225-6760