

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 20 1965
 8-20-65
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Ted Dix of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.Operator's full Name: Skelly Oil CompanyComplete Address: P. O. Box 649, McCook, NebraskaLease Name: Sooter "A" Well No. # 1Location: NW NE SW Sec. 2 Twp. 34 Rge. 14 (E) (W) WCounty Barber Total Depth 4810' Oil WellGas Well Input Well SWD Well D & A X Lost Hole Mr. Dix was instructed to plug the well as follows:

370' of 8 5/8" surface pipe, cemented with 550 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving