

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-1-68

RECEIVED
STATE CORPORATION COMMISSION

SEP 01 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 007 - 20409 - 00 - 00 (of this well)

Operator's Full Name Coin Petroleum Co & Robert-Clarke

Complete Address 780 Farm Credit Bldg Wichita, KS

Lease Name Z Bar Cattle Co Well No. 1

Location 200' W C E/2 SW Sec. 33 Twp. 34 Rge. 15 (E) (W)W

County Barber Total Depth 5082

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation

Address 107 W Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 2:00 PM Day 30 Month 8 Year 1976

The above well was plugged as follows:

97 ft 13 3/8 surface cemented with 150 sacks. 1042 ft 8 5/8 surface
cemented with 500 sacks. 5081 ft 4 1/2 long string cemented with 125
sacks. Top perf. 5041 ft. Sand to 5020 ft, 4 sacks cement with
bailer. Pulled 4200 ft 4 1/2. Set 10 ft rock bridge at 240 ft. Fill
hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-1-76

INV. NO. 3741-W

Signed: [Signature]
Well Plugging Supervisor