



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name American Petrofina Co of Texas

Complete Address Box 1191 Wichita Falls, TX

Lease Name Wells Well No. 1

Location NE/NE/SW Sec. 18 Twp. 34 Rge. 15 (E) (W) W

County Barber Total Depth 5353

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 4:00 PM Day 30 Month 10 Year 1974

The above well was plugged as follows:

262 ft 8 5/8 surface cement circulated. 4850 ft 5 1/2 long string
cemented with 175 sacks. Top perf. 4538 ft. Sand to 4500 ft, 5 sacks
cement with bailer. Pulled 3828 ft 5 1/2. Set 10 ft rock bridge at
240 ft, with 30 sacks. cement. Mud to 40 ft, 10 ft rock bridge, 10
sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/1/74
INV. NO. 224-W