

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 007 - 00483 - 00 - 00 (of this well)

Operator's Full Name Petroleum Management Inc.

Complete Address 200 N. Woodlawn, Suite 201, Wichita, Ks. 67208

Lease Name Davis Well No. A-1

Location C SE NW Sec. 13 Twp. 34 Rge. 15 (E) (W) X

County Barber Total Depth 4880

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

*Plugging Contractor Co. Tools.

Address License No.

Operation Completed: Hour 11:15 Am. Day 29 Month 8 Year 1979

The above well was plugged as follows:

360' 8 5/8" casing w/250 sax cement. 5 1/2" casing set at 4854' w/75
sax cement. Preforated at 4840' to 4846'-Pipe parted at 742'-(Lost-
hole) Howco Mixed & pumped in 8 5/8" casing 5 sax hulls-20 sax gel-
150 sax 50/50 posmix cement w/3% gel to top of casing. Shut in w/100#
pressure. Recovered 742' 5 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-5-79
INV. NO. 0322-4