

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-007-21,234-0001 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Gore Oil Company OPERATOR'S LICENSE NO. 5552 ^{6/90}

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202 PHONE # (316) 263-3535

LEASE (FARM) Alberding WELL NO. 1 WELL LOCATION SW SW NE COUNTY Barber

SEC. 34 TWP. 34S RGE. 12 ~~(E)~~ or (W) TOTAL DEPTH 4825' PLUG BACK TD 4824'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. D-21,117

SURFACE CASING SIZE 10 3/4" SET AT 310' CEMENTED WITH 300 SACKS

CASING SIZE 4 1/2" SET AT 4824' CEMENTED WITH 225 SACKS

PERFORATED AT 4758'-4768' Mississippian; 3570'-3590' Shawnee

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING To pull casing. Sand to 50' above Mississippian perms.

5 sx cement on top of sand. Sand to 50' above Shawnee perms. 5 sx cement on top of

sand. Pump down 10 3/4" - 4 sx cottonseed hulls, 100 sx gel, 50 sx 60/40 Pozmix, (cont'd
(If additional space is needed use back of form.) on back)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 6, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Reh PHONE # (316) 672-3236

ADDRESS Star Route, Pratt, KS 67124

PLUGGING CONTRACTOR Halliburton LICENSE NO. 7718 ¹⁰⁻²⁴⁻⁸⁹

ADDRESS box 963, Pratt, KS 67124 PHONE # (316) 672-5593

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) Wichita, Kansas WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: October 25, 1989

①

Proposed Method of Plugging continued from front:

10 sx gel, 100 sx 60/40 Pozmix to surface.

0000.

0000.

RECEIVED
STATE COMMISSION

OCT 10 1969

WILKINS COUNTY
CONSERVATION DIVISION

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE
JAN 26 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

October 26, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Gore Oil Company
125 N. Market, Suite 1750
Wichita, KS 67202

Alberding 1
SW SW NE
34-34-12W
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760