

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-007-21,266-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Gore Oil Company OPERATOR'S LICENSE NO. 5552

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202 PHONE # (316) 263-3535

LEASE (FARM) Alberding WELL NO. 3 WELL LOCATION SW SE NE COUNTY Barber

SEC. 34 TWP. 34S RGE. 12 (E) or (W) TOTAL DEPTH 4840' PLUG BACK TD 4839'

**Check One:**

OIL WELL ☒ GAS WELL ☐ D & A ☐ SWD or INJ WELL ☐ DOCKET NO. ☐

SURFACE CASING SIZE 10 3/4" SET AT 313' CEMENTED WITH 300 SACKS

CASING SIZE 4 1/2" SET AT 4839' CEMENTED WITH 225 SACKS

PERFORATED AT 4770'-4780' Mississippian

CONDITION OF WELL: GOOD ☒ POOR ☐ CASING LEAK ☐ JUNK IN HOLE ☐

PROPOSED METHOD OF PLUGGING To pull casing. Sand to 50' above perforations, 5 sx cement on top of sand. Pump down 10 3/4" - 4 sx cottonseed hulls, 10 sx gel, 50 sx 60/40 Pozmix, 6% gel, 10 sx gel, 100 sx 60/40 Pozmix, 6% gel to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 6, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Reh PHONE # (316) 672-3236

ADDRESS Star Route, Pratt, KS 67124

Y PLUGGING CONTRACTOR Halliburton Y LICENSE NO. 7718

Y ADDRESS Box 963, Pratt, KS 67124 Y PHONE # (316) 672-5593

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

OCT 26 1989

10-26-89  
CONSERVATION DIVISION  
Wichita, Kansas

SIGNED:

For W. Schuerman  
(Operator or Agent)

DATE:

10-25-89



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

THIS NOTICE

JAN 26 1990

EXPIRES

October 26, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

Gore Oil Company  
125 N. Market, Suite 1750  
Wichita, KS 67202

Alberding 3  
SW SE NE  
34-34-12W  
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*

Shari Feist Albrecht  
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760