

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1967
5-23-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed April 25, 1967

Dear Sir:

Mr. T. D. Sweetman of S & S Drilling Company has this
date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Bldg., Fort Worth, Texas

Lease Name: Hoefle Well No. # 1

Location: C SW SW Sec. 8 Twp. 33 Rge. 13 (E)(W) W

County Barber Total Depth 5220' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

290' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sacks
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent