

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sweetman of Sweetman Drlg Co has this

date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Walter I Phillips & Ferguson Oil Co.

Wichita, KS  
Complete Address: Suite 1025 Garvey Bldg 200 W Douglas

Lease Name: Dugler Well No. 1

Location: SE/NE Sec. 18 Twp. 34s Rge. 9 (E)(W) W

County: Harper Total Depth 5050 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sweetman was instructed to plug the well as follows:

230 ft 8 5/8 surface cemented with 175 sacks. Fill hole

to 200 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

M Russell Bickert  
Conservation Division Agent