



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 9-4-62
 SEP 4 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 8-27-62, 1962, authorized
 the following plugging operation:

Operator's full Name: Wichita Iron & Metal Corp., Inc.

Complete Address: Box 2421 Wichita, Kansas

Lease Name: Morriss Well No. 1

Location: SE SE Sec. 14 Twp. 31 Rge. 9 (E)(W) X

County Harper Total Depth 4500'

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Abandoned Oil Well

Operator was instructed to plug well as follows:

5 1/2" pipe set on bottom. Perforated at 4467'. Sanded to
4450' and 5 sacks cement. 157' of 8-5/8" surface pipe.
Hole filled to 150' with mud, 10' rock bridge and 20
sacks cement. Hole filled to 40' with mud, 10' rock bridge
and 10sacks cement to bottom of cellar.

Very truly yours,

Herman J. Gustus
 Conservation Division Agent