

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 24 1965  
 8-24-65

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Curly Brau of Edmiston Drilling Company has this date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Ks.

Lease Name: Drake Unit Well No. # 1

Location: NW NE SE Sec. 14 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4454' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

235' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 225', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

*Archie Elving*