



15-077-20188-00-00 *CB*

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rankin of Sage Drlg Inc has this

date requested permission to plug the following described well:

Mr. Rankin guarantees payment of the plugging fee.

Operator's full Name: P.O.M. Corporation

Complete Address: Box 374 Ann Arbor, Mich.

Lease Name: Noyer Well No. 1

Location: SE/NE/SE Sec. 31 Twp. 32 Rge. 5 (E)(W) W

County: Harper Total Depth 3918 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rankin was instructed to plug the well as follows:

243 ft 8 5/8 surface cemented with 190 sacks. Fill hole

to 240 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent