



*CPJ*

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Kuhn of Graves Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: E.H. Wood Jr.

Complete Address: 102 E Insurance Bldg. Wichita, Ks

Lease Name: Muir B Well No. 1

Location: NW/NW/NW Sec. 22 Twp. 31s Rge. 9 (E)(W) W

County: Harper Total Depth 4483 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Kuhn was instructed to plug the well as follows:

248 ft of 8 5/8 surface pipe cemented with 250 sacks, &  
50 sacks cement through 2". Fill hole to 245 ft, plug,  
1/2 sack hulls, 25 sacks cement. Mud to 40 ft, plug, 1/2 sack  
hulls, 10 sacks cement to surface. 2 sacks cement in rat  
hole.

Very truly yours,

*[Signature]*  
Conservation Division Agent