

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

NOV 17 1975
11-17-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Atlantic Ritchfield Co

Complete Address Box 521 Tulsa, OK

Lease Name Nora E. Sterling Well No. 2

Location NW 1/4 Sec. 31 Twp. 34 Rge. 12 (E) (W)^W

County Barber Total Depth 4890

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lillard Casing Pulling Co

Address Box 962 Woodward, OK License No. 618

Operation Completed: Hour 3:00 PM Day 14 Month 11 Year 1975

The above well was plugged as follows:
258 ft 10 3/4 surface cemented with 300 sacks. 4889 ft 5 1/2 long
string cemented with 225 sacks. Top perf. 4760 ft. Pump 35 sacks
cement to 4400 ft. Pulled 3100 ft 5 1/2. Pump 65 sacks cement to
208 ft to 308 ft. Plug at 40 ft, 15 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/17/75

INV. NO. 2251-W

Signed: [Signature]
Well Plugging Supervisor