

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
FEB 23 1965
2-23-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Gensch & Holke

Complete Address: 1527 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Davis Ranch Well No. # 1

Location C NW NE Sec. 11 Twp. 34 Rge. 15 (E) (W) W

County Barber Total Depth 4815'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sierra Petroleum Co., Inc.

Address: 1015 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 10:00AM Day 21st Month Feb. Year 1965

The Above well was plugged as follows:

885' of 8 5/8" surface pipe, cemented with 500 sacks. Hole was filled
with drilling mud to 300', 1st cementing plug bridged solid with dry
cement and hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks

I hereby certify that the above well was plugged as herein stated.

DATE 2/24/65INV. NO. 721-WSigned: Archie Elving
Well Plugging Supervisor