

KANSAS

*TY*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 5 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued June 27, 1967.

Operator's Full Name Shenandoah Oil Corporation

Complete Address 406 Mutual Savings Bldg., Fort Worth, Texas 76102

Lease Name Helen M. Smith Well No. # 1

Location App. C SE NW Sec. 25 Twp. 30 Rge. 13 (E) (W)W

County Barber Total Depth 4750'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Clarke Corporation, Inc.

Address Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 12:30 P.M. Day 3rd Month July Year 1967

The above well was plugged as follows:

360' of 8 5/8" surface pipe, cement circulated. 4450' of 4 1/2" long string,  
cemented with 150 sacks. Plug back T.D. 4410'. Top perforation 4358'.  
Bottom of the hole was sanded to 4300', and cemented with 4 sacks, through  
the dump bailer. 3657' of 4 1/2" long string was recovered from the hole.  
Hole was bailed down to 320', bridge plug and rock bridge from 320' to 300',  
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge  
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 7/5/67  
INV. NO. 5520-4