


Form CP-3
Rev. 6-26-62


 KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
 STATE CORPORATION COMMISSION

MAR 21 1966

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name Consolidated Petroleum, Inc.

Complete Address: P. O. Box 14338, Oklahoma City, Oklahoma

Lease Name Davis Ranch Well No. # M-1

Location NE SE NW Sec. 2 Twp. 34 Rge. 15 (E) (W) W

County Barber Total Depth 4932'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No.

Operation Completed: Hour 11:45AM Day 18th Month March Year 1966

The Above well was plugged as follows:

302' of 13 3/8" surface pipe, cemented with 300 sacks. 4882' of 4 1/2" long
string, cemented with 100 sacks. Plug back T.D. 4870'. Top perforation
4849'. Bottom of the hole was sanded to 4800', and cemented with 3 sacks.
4000' of 4 1/2" long string was recovered from the hole. Hole was filled
with mud to 300', rock bridge from 300' to 290', and cemented with 50 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 30 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/21/66

INV. NO. 2894-W

Signed: Aubie Elving
Well Plugging Supervisor