

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wichita Iron & Metal Corp., Inc.

Complete Address: Box 2421 Wichita, Kansas

Lease Name Morris Well No. 1

Location SE SE Sec. 14 Twp. 31 Rge. 9 (E) (W) X

County Harper Total Depth 4500'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 E. 6th Ellinwood, Kansas License No. 396

Operation Completed: Hour 5 pm. Day 31 Month 8 Year 1962

The Above well was plugged as follows:

5-1/2" pipe set on bottom. Perforated at 4450' 4467'. Sanded to 4450'
and 5 sacks cement. 157' of 8-5/8 " surface pipe. Hole filled to 150'
with mud, 10' rock bridge and 20 sacks cement. Hole filled to 40' with mud,
10' rock bridge and 10 sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/5/62
INV. NO. 5632-W

Signed: Herman Justus
Well Plugging Supervisor