

14
KANSAS
STATE CORPORATION COMMISSION

15-077-30012-00-00

CB

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 24 1965
8-24-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas

Lease Name Drake Unit Well No. # 1

Location NW NE SE Sec. 14 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4454'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: E. K. Edmiston Drilling Company

Address: 425 First National Bank Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:00A Day 20th Month August Year 1965

The Above well was plugged as follows:

235' of 8 5/8" surface pipe cement circulated with 200 sacks. Hole was
filled with drilling mud to 225', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 225', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 8/24/65

INV. NO. 1681-W