

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 077 - 20220-00-00 (of this well)

Operator's Full Name Robinson Oil Co.

Complete Address 737 R.H. Garvey Bldg., 300 W. Douglas, Wichita, Ks. 67202

Lease Name Gates Well No. A-1

Location N $\frac{1}{2}$ SW SW Sec. 1 Twp. 34S Rge. 9 (E) (W) X

County Harper Total Depth 4567

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 10 Am. Day 22 Month 4 Year 1980

The above well was plugged as follows:

277' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4560' w/175
sax cement. CIBP set at 4300'-Preforated at 4199'-Sand back to 4150'
Top sand w/ 4 sax mixed cement w/ dump bailer. Pull 3800' casing-
Build bridge at 300'-Dump 5 yard grout in 8 5/8" casing to top of
casing. Hi Grade Ready Mix-Anthony, Ks.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
INVOICED

DATE 4-24-80

INV. NO. 2005-W

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1980
CONSERVATION DIVISION
Wichita, Kansas