



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Robinson Oil Co
Complete Address 340 R.H. Garvey Bldg Wichita, KS
Lease Name Dombaugh A Well No. 1
Location NE/SW/SW Sec. 3 Twp. 34 Rge. 9 (E) (W) W
County Harper Total Depth 4610
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling Co Inc
Address Box 1082 Great Bend, KS License No. 623
Operation Completed: Hour 5:00 PM Day 27 Month 11 Year 1974

The above well was plugged as follows:

241 ft 8 5/8 surface cemented with 175 sacks. 4584 ft 4 1/2 long string
cemented with 135 sacks. Top perf. 4232 ft. Sand to 4100 ft, 4
sacks cement with bailer. Pulled 3800 ft 4 1/2. Set 10 ft rock bridge
at 320 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell B. Buntline*
Well Plugging Supervisor

INVOICED

DATE 12/4/74
INV. NO. 397-W