

R *CPB*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 36 TWP. 33S RGE. 13W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Holmes

Operator Petroleum, Inc. Address 305 East Third, Wichita, Kansas

Field W.C. County Barber

Total Depth 4720 Feet.

Plugging Contractor Garvey Drilling Company

Plugging Contractor's License No. none required - rotary drilled dry hole

Address 305 E. 3rd, Wichita, Kansas

(Describe briefly the manner in which the well was plugged)

283 feet of 8-5/8" surface pipe circulated with cement

Filled bottom of hole with heavy rotary mud from 4720 feet

to 275 feet. Set bottom plug with 1/3 sack of hulls and

20 sacks of cement. Mudded hole to 30 feet; set top plug

with 1/3 sacks of hulls and 10 sacks of cement filling to

base of cellar with cement.

D. S. Guider
District Conservation Agent
for M. A. R. mes

Date March 8, 1956

PLUGGING
FILE SEC 36 T 33 R 13W
BOOK PAGE 44 LINE 13