

15-007-01047-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1964
2-20-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name K & E Drilling Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name Baier Well No. # 1

Location C NE SW SW Sec. 14 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4760

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: K & E Drilling Inc.

Address: 719 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 12:20PM Day 18th Month Feb. Year 1964

The Above well was plugged as follows:

225' of 10 3/4" surface pipe, cemented with 175 sacks. Hole was filled
with drilling mud to 240', 1st cementing plug, bridged solid with hulls,
and cemented with 35 sacks, bringing the top of cement to 170' in the
surface pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls, and cemented with 15 sacks to base
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2-20-64

INV. NO. 8669-4