

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
260 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-077-20211-00-00

LEASE NAME Clements #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NE SE

SEC. 11 TWP. 32s RGE. 7w (E) or (W) (W)

COUNTY Harper

Date Well Completed \_\_\_\_\_

Plugging Commenced 8/1/85

Plugging Completed 9/1/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 4th Finan. Ctr. Wichita, Ks. 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4715'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	225'	none
				5 1/2"	4713'	2640'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3900' & 6 sacks cement. Shot pipe at 3200', 3000', 2800', & 2640'. Pulled 81 joints of pipe. Set rock bridge at 280' & ran 4 yards ready-mix.  
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1985

My Commission expires:



James Hoover  
RECEIVED Notary Public  
STATE CORPORATION COMMISSION

NOV 6 1985

Form CP-4  
Revised 01-84

# GREAT GUNS

(2/12/73)

4673  
9257  
471537

FILING NO. \_\_\_\_\_

COMPANY BEREN CORPORATION

WELL CLEMENTS NO. 1

FIELD HARPER

COUNTY HARPER STATE KANSAS

LOCATION: C-NE-SE  
SEC. 11 TWP. 32S RGE. 7W

OTHER SERVICES: \_\_\_\_\_

PERMANENT DATUM GROUND LEVEL ELEV. N/A ELEV. K.S. N/A  
LOG MEASURED FROM KELLY BUSHING 5 FT. ABOVE PERM. DATUM D.F. N/A  
DRILLING MEASURED FROM Kelly Bushing O.I. N/A

DATE	12-12-73	12-12-73	
RUN NO.	one	one	
TYPE LOG	gamma	neutron	
DEPTH-DRILLER	<u>4715</u>	4683	
DEPTH-LOGGER	4683	4683	
BOTTOM LOGGED INTERVAL	4674	4682	
TOP LOGGED INTERVAL	000	000	
TYPE FLUID IN HOLE	water		
SALINITY, PPM CL			
DENSITY			
LEVEL	full		
MAX. REC. TEMP., DEG F.			
OPERATING RIG TIME	Port Mast		
RECORDED BY	Robben		
WITNESSED BY	Mr. Chambers		

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1985  
CONSERVATION DIVISION  
Wichita, Kansas

RUN NO.	BORE-HOLE RECORD			CASING RECORD			
	BIT	FROM	TO	SIZE	WGT.	FROM	TO
				8 5/8	28	000	225
				5 1/2	14	000	4713

*Pipe 3960-3966'*  
*320 sacks Cement*