

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 2 TWP. 32S RGE. 8WE/W
Location as in quarters or footage from lines:

300 - NE of C - NE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Robinson Oil Company
Lease Name Troyer Well No. A-1
Office Address R. H. Garvey Building, 300 W. Douglas, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed _____
Application for plugging filed 9-23-81
Plugging commenced _____
Plugging completed 10-7-81
Reason for abandonment of well or producing formation _____

Not Productive

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	258	None
				4 1/2	2878	2090

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Plug back at 2715

Dumped sand from 2715 to 2280

4 sacks cement from 2280 to 2240

Ripped pipe at 2090 - Pulled 4 1/2"

Allied pump in - 15 sacks Jell

- 8 sacks Hull

- 10 sacks Jell

- 125 sacks 50-50 POZ 4% Jell 3% c.c.

STATE RECEIVED
CORPORATION COMMISSION
OCT 9 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber ss.

Elmer R. Marguette (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Marguette
Medicine Lodge, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October 1981

Jessie Hamilton
Notary Public.

My Commission expires: April 4, 1982

WELL LOG
Troyer A #1
NE NE 2-32-8W
Harper County, Kansas

Name of Operator: Robinson Oil Co.
340 R. H. Garvey Bldg.
Wichita, Kansas 67202

Date Completed: December 13, 1975

<u>FROM</u>	<u>TO</u>	
0	570	Red bed and shale
570	1250	Shale
1250	3634	Lime and shale
3634	3755	Stal. Sand
3755	4409	Lime and shale
4409	4500	Miss.
4500		Total Depth

STATE OF KANSAS


COUNTY OF BARTON ss

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1981

CONSERVATION DIVISION
Wichita, Kansas

Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.


Gary L. Hawk

Subscribed and sworn before me this 23rd day of December, 1975.


Notary Public Barton County

My Commission Expires 7-10-77

