

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 35 TWP 32S RGE 7W E/W
Location as in quarters or footage from lines:
NW NW SE

Lease Owner Kelso Casing Pulling
Lease Name Prouse 1-35 Well No. _____
Office Address Box 176 Chase, Kansas 67524
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4-26-82
Plugging completed 5-3-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? XXXXXXXXXXXXX Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4910'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	291'	none
				4-1/2"	4593'	3989'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4450' and ran 4 sacks cement. Shot casing @4018' and
pulled a total of 97 joints of 4-1/2" casing. Plugged well with 15 sacks gel, 6 sacks
hulls, 10 sacks gel, 8-5/8" plug, 125 sacks ~~XXXX~~ cement, 3% cc.

Plugging Complete

RECEIVED

(If additional description is necessary, use BACK of this sheet) STATE CORPORATION COMMISSION
Name of Plugging Contractor Kelso Casing Pulling

MAY 10 1982

STATE OF Kansas COUNTY OF Rice, ss.

CONSERVATION DIVISION

R. Darrell Kelso
(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 82



My Commission expires:

Irene Hoover
Notary Public.

DRILLERS LOG

OPERATOR: Rine Exploration, Suite 645
 300 West Douglas
 Wichita, Kansas 67202

WELL NAME: #1-35 Prouse
 NW NW SE Sec. 35-32S-7W
 Harper County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 3/30/81

COMPLETED: 4/11/81

RTD: 4910'

SURFACE CASING: 8-5/8" set at 291' with 225 sx cement

PRODUCTION CASING: 4-1/2" set at 4593' with 150 sx cement

0' to 294' 12 1/2" Surface Hole
 294' to 1150' Red Bed-Shale
 1150' to 1410' Red Bed-Lime & Shale
 1410' to 3625' Lime & Shale
 3625' Lime & Shale - Stalnaker Sand
 3625' to 3990' Lime & Shale (K.C.Limestone)
 3990' to 4110' Kansas City Lime
 4110' to 4370' Lime & Shale
 4370' to 4755' Lime & Shale (Mississippian)
 4755' to 4860' Lime
 4860' to 4910' Lime & Shale
 RTD 4910'

RECEIVED
 STATE CORPORATION COMMISSION
 APR - 5 1981
 CONSERVATION DIVISION
 WICHITA KANSAS

STATE OF KANSAS
 COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
 hereby state the above is an accurate copy of the #1-35 Prouse log for
 Rine Exploration.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me
 this 21st day of April, 1981

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1985

