

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Harper

County. Sec. 34 Twp. 32S Rge. (E) 7 (W)

NORTH

X			

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Gulf Oil Corporation
Lease Name L. W. Bartlett Well No. 1
Office Address Box 661, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-18 1954
Application for plugging filed 6-22 1955
Application for plugging approved 6-24 1955
Plugging commenced 7-10 1955
Plugging completed 7-12 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well PB 4734 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"	4831'	3561'
				8-5/8"	316	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with chat to 4470' and spotted with 5 sacks cement. Mudded hole to 270' of surface., bridged with rock and spotted 20 sacks cement. Mudded to 35' of surface bridged with rock and capped with 10 sacks cement filling into cellar.

RECEIVED
STATE CORPORATION COMMISSION
7-22-55 JUL 22 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Morgan Well Plugging Service
Address 102 W. 18th, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
W. H. Duley (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1955

My commission expires April 24-1956 Notary Public.

7-19-55
:jrm.

PLUGGING
FILE SEC 37 T 32 R 74
BOOK PAGE 129 LINE 16

WELL RECORD

GULF T 880-A PRINTED IN U.S.A.

WELL NO. 1 LEASE L. W. Bartlett COMPANY Gulf Oil Corp. A.F.E. 3395

DATE-DRILLING BEGAN 8-2-54 temporarily abandoned
WELL COMPLETION 10-18-54 FIRST PRODUCTION -

SAND RECORD Dry Hole - Temporarily Abandoned TOTAL DEPTH 4871
28 From 4608

INITIAL PRODUCTION

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LOS. CAL. CHLO.	PULLED	LEFT IN
8-5/8	*	*	*	*	316	200			316
5-1/2	14	SR	A	ES	4831	250			4831
4	11			(Hydrill Liner)	4888	30		(91" Liner)	91

NOTE: 3jts-32"-10V&SR- Cl. C-1 - LW
6jtc-22.75"-IT - A - GH

S- 34 T- 328 R- 70

		Center
		LW
		GH
		SR
		Harrier
		County
		Kansas

Distance H: 13' from RKB to top of 8-5/8" casing head flange.

ELEVATION- 1140' IS

Treated w/500gals acid, then w/1000 gals acid.

Perf 4839-4840' w/2 shots } - squeezed w/178 sacks cement, re squeezed w/50 sacks cement.
Perf 4852-4853' w/2 shots }
Perf 4846-4847' w/4 shots

FORMATION RECORD

	FROM	TO
Clay	0	40
Sh, lm, shells		260
Sh, shells, rd rock		390
SR, rd rock		575
SR		940
Sh, shells		1005
Anhydrite		1030
Sh, lm		3580
Sh		3640
Sd		3711
Ln, sh		3950
Ln		4129
Ln, sh		4445
Mississippi line		4695
lm, sh		4819
Sh		4830
Viola		4838 TD

PLUG BACK & TEST: 12-27-54 to 1-12-55 AFE #3542
DEPTH: Plugged back from 4871' to 4734'
CASING: 5 1/2" Perforated 4479' to 4486' with 4 jet shots/foot

ACIDIZED: 375 gal wash acid and 250 gal mud acid 1-8-55
PRODUCTION: Before swabbed "Dry"
After swabbed "Dry"

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34 T 32 R 70
PAGE 129 LINE 16