


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Harper County. Sec. 20 Twp. 32S Rge. 6 (E) 6 (W)
Location as "NE/CNW&SW" or footage from lines. SE SE SW
Lease Owner Dorset Co.
Lease Name Carothers Well No. 1
Office Address 610 National Bank of Tulsa Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-17-59 19
Application for plugging filed 3-17-59 19
Application for plugging approved 3-17-59 19
Plugging commenced 3-17-59 19
Plugging completed 3-17-59 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lewis Brock
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4870' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 4870' to 185'
Cement 185' 140'
Mud 140' 40'
Cement 40' 0'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor McKnab - Lindsay (Rotary Plugged)
Address Box 808, Winfield, Kansas

STATE OF Kansas, COUNTY OF Cowley, ss.
V. W. McKnab (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. W. McKnab
Box 808, Winfield, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 59

My commission expires Aug. 21, 1961

Melvin Liebau
Notary Public.

PLUGGING
FILE SEC. 20 T. 32 R. 6W
BOOK PAGE 23 LINE 14

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1959
CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD
Carothers #1
SE SE SW 20-32S-6W
Harper County, Kansas

Operator: Dorset Co.
Contractor: McKnab - Lindsay

Date Comm: 2-27-59
Date Under Surf: 2-28-59
Date Comp: 3-17-59

DRILLER'S LOG

0 - 1240	Shale
1240-3133	Shale & Lime
3133 - 3250	Sandy Shale & Lime
3250 - 3337	Lime & Shale
3337 - 3399	Lime
3399 - 3524	Shale
3524 - 3690	Sand & Shale
3690 - 3845	Lime & Shale
3845 - 4193	Lime
4193 - 4300	Lime & Shale
4300 - 4354	Lime
4354 - 4409	Lime & Shale
4409 - 4435	Lime
4435 - 4439	Shale
4439 - 4768	Lime
4768 - 4842	Lime & Shale
4842 - 4861	Shale
4861 - 4870	Sand
4870	T.D.

Casing & Cement record:

9 Jts. 182' 8 5/8" 10 Thrd. Casing
Set at 192' with 1 Centralizer
and cemented with 140 sks. HA 500

Plugging Record:

Mud from 4870 to 185'		
Cement	185	140
Mud	140	40
Cement	40	0

Acknowledged:

McKnab - Lindsay

By J.W. McKnab

March 18, 1959

Subscribed and sworn to before me this 18th day of March, 1959.

Melvin L. Libau
Notary Public

My commission expires Aug. 21, 1961.

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 20 T. 32 R. 6 W
BOOK PAGE 23 LINE 14