

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper

County, Sec. 14 Twp. 31 Rge. 9 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/SE/SE

Lease Owner Aurora Gasoline Company

Lease Name Morris Well No. #3

Office Address 1107 Un. Natl. Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed Yes 19__

Application for plugging approved Yes 19__

Plugging commenced _____ 7-27 19 58

Plugging completed _____ 8-1 19 58

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		3,525'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 4500'.

Plugging started 7-27-58. Finished 8-1-58.

Plugged off bottom and sanded back to 4375'. Dumped 5 sacks cement.

Shot 5 1/2" casing at 3,525'. Pulled pipe out of hole and plug stopped at

235'. Squeezed well as follows: Mixed 20 sacks gel and 75 sacks cement. Mixed 15 sacks cement for cap on well. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) J.O. Forbes

Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1958

My commission expires November 8, 1960

Betty S. Edman
Notary Public.



PLUGGING
FILE SEC 14 T. 31 R. 9W
BOOK PAGE 117 LINE 21

AUG 16 1958
8-16-58
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Main Street, Wichita, Kansas

COPY


Company- HERWICK & AURORA GASOLINE
Farm- Morris No. 3

Sec. 11 T. 31 R. 9W
NE SE SE

Total Depth. 4500'
Comm. 11-26-54
Shot or Treated.
Contractor.
Issued. 8-4-56

Comp. 12-9-54

County Harper
KANSAS



Elevation. 1617 RB

Production. 334 BO

CASING:

8" 167'
5" 4500'

Figures indicate Bottom of Formations.

salt-sand	120
shale shells	187
shale-red rock	650
shale shells	950
shale shells	1200
lime	1225
shale shells	1850
shale-lime	1935
lime	2035
shale	2830
shale-lime	3180
lime	3525
shale	3598
sand	3614
lime-shale	3628
lime	4500
Total Depth	

TOPS: Scout	
Anhydrite	1195
Mississippi	4363

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1962
CONSERVATION DIVISION
Wichita, Kansas