

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,864-0000

LEASE NAME Morton "B"

WELL NUMBER #4

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 12 ~~0000~~ (W)

COUNTY Barber

Date Well Completed 7-19-84

Plugging Commenced 4-11-90

Plugging Completed 4-17-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, Suite 1750, Wichita, KS 67202

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-3-90 (date)

by Dodge City (KCC District Agent's Name)

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4752' Bottom 4768' T.D. 4839'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	803	8 5/8"	803	0
		0	4849	4 1/2"	4849	3480

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug back with sand to 4700'. Dump 4 sx cement. Plug with 300# hulls, 10 sx gel, 50 sx 60/40 - 6%, 100# hulls, 10 sx gel, 100 sx 60/40 - 6% to surface. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address Box 187, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~xxx Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) 125 N. Market, #1750, Wichita, KS



SWORN TO before me this 23rd day of April, 19 90
Rebecca K. Crawford
 Notary Public
 My Commission Expires: 1-7-91