

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-007-22656-00-00

LEASE NAME Burgess "A"

WELL NUMBER 1

1755 Ft. from N Section Line

790 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-18-02

Plugging Completed 6-20-02

RECEIVED  
JUL 10 2002  
7-10-02  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR LOTUS OPERATING CO., LLC

ADDRESS 100 S. Main, Suite 520 Wichita, Ks. 67202

PHONE (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Oil

(i.e., Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

Scott Alberg (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 5186

Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1047'	None
				4-1/2"	4967'	3520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4600' and 4 sacks cement. Shot pipe loose @3520', pulled up to 1080', pumped 50 sacks cement and 15 sacks gel, pulled up to 600', pumped 40 sacks cement, pulled up to 250' and circulated 40 sacks cement to surface. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Company, LLC

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of July, 2002

[Signature]  
Notary Public

My Commission Expires:

